



Alabama State Port Authority
Addendum to R&P or Specification Booklet

Project Name McDuffie Terminal – Roof Replacements


Project No. 10870

Addendum No. 4

To: Prospective Bidders

Date: 2/8/2023

The Requisition and Proposal is amended as follows.

Item	Description
1.	<p>Note is made that the Southwest Building has two roofs. See the attached photo as information. Both roofs will be required to be removed down to the concrete deck prior to installation of the new roof.</p>  <p>The photograph shows a hand holding a rectangular piece of green, fibrous material that is peeling and flaking. This material is being held over a rectangular hole in a concrete surface. The hole is filled with dark gravel. The surrounding concrete surface is covered with a light-colored, woven fabric mesh. The background is a plain, light-colored wall.</p>
2.	<p>The buildings are required to be kept watertight and free from construction materials entering the buildings at all times. At a minimum, a vapor barrier base sheet or approved equivalent must be installed/attached to the concrete deck prior to the installation of the insulation and 2 ply SBS Modified Bitumen roofing system. This requirement does not relieve the requirement of the Contractor to keep the building watertight during construction nor to provide a complete working roofing system.</p>



Alabama State Port Authority
Addendum to R&P or Specification Booklet

3. As part of the project, the HVAC curbs shall be replaced in like kind as original. The curbs shall be a minimum eight (8) inches tall. A marked-up photo below is attached as an example but is not necessarily representative of every building.



Please indicate your receipt of this addendum by adding the addendum number in the appropriate place in your Requisition & Proposal or Specification Book.

Project Manager:

James J. "Josh" Bell, P.E.
Facilities Engineer

2/8/2023

Date