Project Name **Building 55 Exterior Sealing and Painting**

Location **Mobile, AL**

Project # **11360 Task 1** **November 2023**

First Addendum

Building 55 Exterior Sealing and Painting

November 13, 2023

ALABAMA PORT AUTHORITY
PORT OF MOBILE

First Addendum

Project Name	**Building 55 Exterior Sealing and Painting**
Location	**Mobile, AL**
Project #	**11360 Task 1 November 2023**

The project specifications shall be amended to include power washing, painting the window frames and other items as follows:

1. Preparation shall include power washing of building, adjacent concrete sidewalks, concrete pads, and the building exterior surfaces except for the roof.
2. Preparation shall include caulking around all window and door openings.
3. Crack filler / caulk shall be Loxon S1 One Component Smooth Polyurethane Sealant.
4. Priming shall include applying appropriate Owner approved metal primer to all metallic surfaces including aluminum window frames and steel lintels.
5. If winning Bidder is also awarded other painting project(s) by the Owner, the work may be scheduled sequentially rather than concurrently.